

MSFC ROUTING SLIP					
	CODE	NAME	INIT.	<input checked="" type="checkbox"/> ACTION	<input type="checkbox"/> INFORMATION
1	I-RM-D	Mr. Cropp			
2					
3					
4					

REMARKS

SUBJECT: Draft Script Saturn I/IB Quarterly Film
Report No. 25

Lee:

Due to time limitations and knowledge that you were working on pages 4 through 8, I did not review those pages, nor the engine section on pages 18 and 19.

Return of this draft script with suggested corrections is in no way to be interpreted as script approval even after indicated revisions are made. Please furnish I-I/IB-C with a revised draft script as soon as possible so that necessary concurrence can be obtained from Saturn I/IB elements.

CODE I-I/IB-C	NAME G. Ladner	DATE 10/1/65
------------------	-------------------	-----------------

MSFC - Form 183 (Rev. February 1961)

DRAFT SCRIPT

for

SATURN I/IB QUARTERLY FILM REPORT

NO. 14 25

(Covering July, August, September, 1965)

FILM

Scene 1--

NASA Seal

Scene 2--

"The George C. Marshall Space

Flight Center Presents"

Scene 3--

Artwork, the pop-on words over
artowrk, "Saturn I/IB"

Scene 4--

Preparations for launch of SA-10.

Show delivery, inspection, checkout,
and assembly of components for SA-10.

NARRATION

Saturn I/IB Quarterly Film

Report No. ²⁵~~24~~ covers progress

during the period July, August,
September, 1965.

Highlighting this quarter was

the successful launch and flight

of the tenth Saturn I, SA-10, and ^{successful}
~~closing out the Saturn I launch vehicle~~
~~the third successful orbiting of~~
~~program with 19 successful out of 12 scheduled~~
~~a Meteoroid Technology Satellite.~~

Late last quarter, launch vehicle

~~had been erected~~
~~erection was completed at the~~
~~pre-launch testing started~~
Cape and was being tested. The

spacecraft (consisting of Pegasus

C within the Boilerplate plate

Service Module ^{plus the} and Command Module ^{the})

was erected atop SA-10. ^{on July 2}

FILM

Scene 5---

Show SA-10 on pad.

Show countdown demonstration

scenes, then back to SA-10

on pad.

Countdown activity (Blackhouse Scenes)

Scene 6---

Show SA-10 on launch pad prior to

engine ignition, show brief count-

down activity; then back to SA-10 on

pad.

Scene 7---

Engine ignition, vehicle release,

liftoff, tracking sequence.

NARRATION

The overall flight objectives of

SA-10 were to: provide and evaluate

meteoroid data in near-earth orbit;

continue development of ^{the} launch

vehicle iterative guidance mode;

and continue evaluation of system

accuracy; ^{Meteoroid Technology} and place the ^{Popstar} satellite

in near earth orbit. The function of the Popstar is to provide meteoroid data on near-earth space.

Pre-launch checkout of SA-10

progressed satisfactorily. Follow-

ing checkout, countdown demonstration

testing was successfully completed.

Countdown began within the scheduled

time frame.

SA-10 liftoff occurred July 30th

at 8 a.m., Eastern Standard Time.

^{Suborbital} SA-10, the second vehicle to use

an industry-produced booster

marked a record of ten-out-of-ten

highly successful flights.


FILM

Scene 8---

Show first stage burnout, then follow-up with second stage ignition and flight.

Scene 9---

Kinescope on Pegasus B sequence
(Note: no onboard camera footage for Pegasus C).



Scene 9.1---

Use time effect to describe to Saturn I in flight.

NARRATION

The first stage burned for 148 seconds, ^{separated and fell away.} and separation was good.

^{Douglas-built}
The second stage burned about 480 seconds, obtaining programmed cutoff velocity. Stage performance was ^{nominal} ~~satisfactory~~ and marked a six-^{in the required orbit.} ~~out-of-six record for a Saturn~~.

S-IV stage.

(The following scenes are from Pegasus C kinescope)

The Apollo Command and Service Module jettisoned mechanically, ^{and} like its predecessors, Pegasus C's wings ^{were} ~~successfully~~ deployed. Pegasus C is presently obtaining information concerning quantity and penetrating ability of meteoroids in ~~the~~ near-earth's ^{space} orbit.

^{successful}
The launch of the tenth and final

Saturn I launch vehicle, SA-10, ^{closed out one of the most successful R&D} ~~brought to a close NASA's most~~ programs in the history of rocketry. The ~~successful rocket program - a~~ program, conceived to deliver a heavy launch vehicle

^{on the road to the moon with ten} ~~on the road to the moon with ten~~ of 10 scheduled launches.

FILM

Scene 10---

ABMA film showing Dr. von Braun and General Medaris looking over blue-prints and drawings related to Saturn rocket.

Scene 11----

Footage showing men examining blue-prints, existing facilities, equipment and models of vehicles.

NARRATION

The Saturn program has provided more than a history of straight successes. Saturn I has launch vehicle. It has provided the technological recorded an enviable list of accomplishments in its five-year launch history having its beginning.....

at the Army Ballistic Agency
The Saturn I program began in 1958

.....in September 1958, under the

leadership of Dr. Wernher von Braun

Major and General John Medaris, *The purpose of the program, under ARPA Order 14-59, was to develop a flight program was started within a little a 1 1/2 million-pound-thrust, clustered-engine first stage. Shortly thereafter, the program was expanded to the development of a 2 million-pound-thrust, clustered-engine first stage.*

During the next few months, *studies* a study *were* was made to determine the most ex-

peditious manner for using existing

tooling, hardware and facilities;

the new facilities were required for and to formulate a plan to meet

future requirements - which would

include the technical knowledge of

of these studies was the result of a contract various contractors.

to the Douglas Aircraft Co to develop and manufacture the second stage. Design immediately began work.

FILM

Scene 12---

Footage showing official transfer of Saturn program from Department of Defense to NASA.

Scene 13----

Footage showing various stages of first Static Test Vehicle.

Scene 14----

Show static firing of first Static Test Vehicle.

Scene 15---

Assembly of SA-1
(Stock footage) follow-up with flight qualification testing of stage.

development - the first stage. The stage consisted of a cluster of nine tanks and eight H-1 engines. The engines were an improved version of the engine used for the Jupiter and other military missiles. The first stage manufactured was a static firing test stage.

5

NARRATION

During March 1960 technical and administrative

The Saturn I development program, control of the Saturn Program was transferred from begun by the Department of Defense, ARPA to NASA. In July, the General Counsel was transferred to NASA in 1959. In Space Flight Center was established. The nucleus early 1960, the Marshall Space Flight Center was formed.

Under the direction of Marshall, fabrication and assembly of a ground test first stage was started.

In April 1960, successfully static testing was performed on the stage. Modifications, design changes, and additional firings were conducted to

insure a more reliable vehicle. A final acceptance firing was held in late 1962.

Two months later, assembly of the first stage, SA-1, got underway.

Following final assembly and flight qualification testing, the first Marshall-built booster was shipped to Cape Canaveral, August 1961.

It was shipped by barge, specially built or modified to move the large first stage.

FILM

Scene 16----

Flight of SA-I

(Stock footage)

Scene 17---

Flights of SA-2, 3, and 4.

(Stock footage)

Scene 18---

Footage on assembly and
testing Douglas' S-IV stage, ship-
ment of stage and erection atop
S-I-V.

(Stock footage)

NARRATION

At Cape Canaveral
SA-I was ~~then~~ erected on the pad
with ~~using dummy~~ upper stages, water
ballasted.

At 10:06 a.m., October 27, 1961,
the first Saturn I was launched.
The flight lasted eight minutes and
was considered highly successful.

Another Saturn I was launched
April 25, 1962; a third, November
16, 1962; and a fourth, March 28,
1963. Flight testing of these

vehicles allowed for the continual
development of the first stage,

including engine-out capability,
~~propulsion system and instrumentation;~~
~~testing of guidance and instrumenta-~~
~~tion and verification of launch sup-~~
~~port equipment.~~

(A developed engine out capability would allow the
Saturn to complete its mission with the loss of one
engine by diverting propellant to the remaining
engines.)

Meanwhile, the Douglas Aircraft Co.
continued assembly on a live upper
stage, called the S-IV. Following

testing and acceptance, Douglas shipped
the Marshall-ordered second stage to

FILM

Scene 19---

Flight of SA-5

(Stock footage)

Scene 20---

Flight of SA-6

(Stock footage)

Scene 21---

Flight of SA-7

(Stock footage)

Scene 22---

Flight of SA-9

(Stock footage)

NARRATION

for mating with the people
the Cape to be placed on top of the
Saturn I and stage (The 5-12 stage is
fifth Saturn booster.
placed on top of the 5-12 stage and stage 15
hydrogen peroxide; produced on 2-10-64
9, 000 pounds. This was the first time
any time before proper
SA-5 was launched January 29, 1964.

It made a near perfect flight,
placing more than 37,000 pounds
into earth orbit. *Other*
first time, proper
use of 20 100.

A sixth Saturn was launched May 28,th
1964, again with the first and second
stages live; and again with a payload
exceeding 37,000 pounds. Part of
this orbiting package was ^{an} early
model of an Apollo spacecraft. The
flight of SA-6 terminated the Saturn
I R&D flights. *SA-6 was the*

SA-7, the first operational flight
vehicle, was launched September 18,th
1964, and was highly successful.
All major test objectives were met.

SA-9, launched on February 16, 1965,
placed into orbit a Pegasus Meteoroid
Satellite, designed to obtain

FILM

Scene 23---

Show assembly, checkout
and test of the booster for
SA-8. Follow-up with launch of
SA-8

Scene 24---

Flight of SA-8

NARRATION

information concerning quantity and
penetrating ability in the near-
earth orbit. The satellite was
developed by Fairchild-Hiller,
under MSFC management, for NASA's
Office of Advanced Technology.

The SA-8 booster was assembled,
checked out, and tested at Marshall's
Michoud Facilities. The Chrysler-
built booster was the first industry
produced first stage.

SA-8 was launched May 25, 1965.

It was the ninth straight successful
Saturn - placing the second meteoroid
satellite in near-earth orbit.

SA-10's flight closed the Saturn I
program with a completely successful
record. The Saturn I program enabled
great strides in guidance, instrumen-
tation and aerodynamic capabilities
already proved useful in the Saturn
IB program.

Marshall and its contractors are
describing the first launch of a Saturn
for example

FILM

Scene 26---

S-IV-201 component
assembly and checkout

Scene 27---

IV Checkout Station at IBM.

Scene 28----

Input from Douglas on
S-IVB-201

NARRATION

Component ^{installation} ~~assembly~~ for the first ^{flight} Saturn IB Instrument Unit, designated 201, was completed August 26th.

Activation of IBM's Checkout Station was accomplished with checkout of ^{IV} ~~IV~~-201. Checkout continued through September with shipment to KSC scheduled for October.

On August 4th, at Douglas' SACTO Facility, S-IVB-201 underwent two unsuccessful long-duration firings. Four days later, the stage was successfully fired for a period of 453 seconds. Post-static operations were then conducted through August 15th. The stage was removed from the Test Stand August 28th and preparations for shipment begun. On September 3rd, the stage was barged from SACTO and later shipped by sea to KSC, arriving September 18th.

FILM

Scene 29---

Chrysler input showing final checkout of S-IB-1, shipment from Michoud and arrival at KSC.

Scene 30---

Cape input showing S-IB-1 in Hangar AF. Followup with stages of erection into tower on L.C. 34.

NARRATION

It was housed in Hangar AF where structural modifications and repair of debonded insulation is in process.

S-IB-1 post-static checkout, started last quarter, was completed July 19th. Preparation for stage shipment from Chrysler-Michoud to KSC continued from mid-July through August 9th. It was shipped the same day arriving at the Cape August 14th.

The stage was moved into Hangar AF for fin installation. On August 11th it was erected on Launch Complex 34. About ten days later, stacking of the second stage, instrument unit and ~~Boilerplate~~² Apollo was completed in preparation for facilities check-out to prove compatibility of both the launch vehicle and launch facilities.

FILM

Scene 31----

Show modifications and re-installation of upper stages on Saturn IB Dynamic Test Stand

Scene 32----

Saturn IB Dynamic testing

Scene 33---

Conversion from Saturn IB hardware to Saturn V hardware configuration.

Scene 34---

Stock footage of structural testing of S-IV-200/500S at MSFC

NARRATION

At Marshall's Saturn IB Dynamic Test Area, modifications to the Test Stand, changeover to upper stage configuration, and re-installation of upper stages was completed July 29th.

Upper stage dynamic testing continued through the quarter with completion of testing September 11th.

Following successful IB dynamic testing, conversion to Saturn V hardware configuration for use in Saturn V Dynamic test Program got underway.

Structural testing of the first three instrument units built by General Dynamics was successfully completed July 22nd.

FILM

Scene 35---

IBM input on NAA,
built structural test
unit

Scene 36---

Static firings at Marshall
on S-IB-2. Input from
Chrysler.

NARRATION

The second in a series of structural test units assembled by IBM/Huntsville - using segments manufactured by North American Aviation, was rejected by MSFC due to discrepancies. Following necessary re-tooling, a second unit was assembled and delivered September 30th. Preparation for testing and structural testing will start next quarter.

At Marshall, S-IB-2 underwent two successful routine static firings, the first on July 9th, the second on July 20th. The stage was then shipped to Michoud August 1st, arriving August 6th. Modification and repair to the stage continued throughout the quarter, until post-static checkout began date September. Delivery to KSC is scheduled for mid-December.

FILM

Scene 37---

Input from Chrysler
on S-IB-3.

Scene 38---

Input from Chrysler on
S-IB-4

Scene 39---

Input from Chrysler
on S-IB-5

Scene 40---

Input from Chrysler
on S-IB-6 and S-IB-7

NARRATION

Also, at Chrysler, Michoud,
S-IB-3 checkout, started late
last quarter, was completed August 14th.
Preparations for stage shipment to
Marshall continued to September 9th.
It was shipped by barge the same day
arriving September 16th. Static
testing is scheduled for October.

S-IB-4 assembly was completed in
September. Pre-static ^{checkout} of the
stage got underway September 13th and
continued through the quarter.

Stage fabrication for S-IB-5 was
completed July 15th. Tank
clustering started the same day
and was completed in mid-August.
Stage assembly continued through
remainder of quarter.

S-IB-6 Stage fabrication, started
last quarter, continued through this
period with tank clustering expected
to begin next quarter.

FILM

Scene 41---

Input from Douglas on

S-IVB/202.

Scene 42---

Input from Douglas on

S-IVB/203

NARRATION

S-IB-7 fabrication started

August 19th with fabrication of the lower thrust ring. Fabrication of the upper thrust ring began August 26th.

All work effort continued through the remainder of the quarter.

At Douglas' Huntington Beach Facility, S-IVB/202 checkout was terminated August 12th. It was shipped aboard the NASA barge "ORION" August 28th; arriving Courtland Dock 3 days later. The stage was offloaded and installed in Beta Test Stand No. 3 the morning of September 2nd. Pre-firing operations are in process - with static firing and delivery to Cape Kennedy scheduled for next quarter.

S-IV-B/203 checkout, begun August 14th was terminated August 28th. The stage underwent final component installation through September 17th. The next day it was returned to the tower for combined manufacturing and checkout.

FILM

Scene 43---

Input from Douglas

on S-IVB/204

Scene 44---

Input from Douglas

on S-IVB/205

Scene 45---

Input from Douglas on

S-IVB/206

NARRATION

S-IVB/204 assembly operations, started last quarter, continued with joining of the forward and aft skirt and thrust structure in early September. On September 20th a J-2 engine was installed. System check-out started last quarter and will continue next period.

LOX and LH₂ tank installation for S-IBV/205^B was completed this quarter. Insulation of the stage's LH₂ tank was completed in early September. Modifications and repair are in process.

S-IVB/206 work progress continued with joining of the forward and aft common dome to form the common bulkhead. Assembly of the LOX tank was completed in mid-September. The stage was then shipped from Santa Monica to Huntington Beach for assembling the LH₂ and LOX tanks in the tower.

FILM

Scene 46---

Input from Douglas on

S-IVB/207

Scene 47--

Douglas input showing

work on Beta Stand No. 1.

Scene 48--

Stock footage showing component assembly of an IV.

NARRATION

Stage fabrication, for S-IVB/207 began early this quarter. Contractor efforts showed that by mid-September welding of the forward and aft common dome was completed. The domes went to the insulation bonding room for honeycomb insulation and bonding to form the common bulkhead.

Following completion of Saturn V S-IV-B Battleship testing August 20th, preparations began for converting the stand for checkout and static firing S-IVB flight stages. Additional checkout equipment will be installed on the stand prior to the erection of the first flight stage, S-IVB/203.

At IBM, Huntsville, ^{IV}S-IV/202 component assembly, started last quarter, continued through September, with completion and checkout scheduled for next quarter. Shipment to the Cape is scheduled in December.

FILM

Scene 49--

Stock footage showing
structural and component
assembly of an IV

Scene 50--

Cape input on Ground Support Equipment
for VLF-34

Scene 51--

Static firing of J-2
engine in MSFC's S-IVB
Battleship Test Stand.

NARRATION

^{IV}
S-IV-203 structural assembly was
completed in early September.
Component assembly is in process with
completion of assembly and unit
checkout scheduled for next quarter.
^{IV}
S-IV-204 structural segments fur-
nished by North American Aviation were
received at IBM September 15th and are
now in receiving inspection.

At KSC, mechanical system equipment
was delivered during this quarter for
use at VLF-34. Most electrical system
equipment has been received to date.
Installation of GSE is scheduled for
completion next quarter.

At Marshall, the second J-2 engine
delivered by Rocketdyne underwent
initial static firing during August
in the Center's new S-IVB Battleship
Test Stand.

FILM

Scene 52---

J-2 engine static firing
at Sanata Susana
(Stock footage)

Scene 53---

Additional J-2 engine
firings

Scene 54---

J-2 Product-improvement
program
OM-1869 (Confidential)

NARRATION

Rocketdyne's J-2 Engine Flight Rating Test series, begun last quarter, was completed July 21st at Santa Susana. Twenty-five firings were conducted for a total performance of 46 minutes. Deficiencies will be corrected prior to completion of engine qualification. FRT Engine Nr.2003 was disassembled for engineering inspection in August.

Engine Nr.2032 was acceptance tested and 200K Qualification Test Series began at Delta Two Test Stand in August. Qualification tests are due to be completed late next quarter.

Rocketdyne's J-2 product-improvement program included the manufacturing of a new canted-choke ring to offset the opening towards the turbine inlet, with the desired effect of reducing skin temperatures. A test run with the standard ring produced skin temperatures up to 1700 degrees Fahrenheit in the combustion zone. A test

FILM

Scene 55--

OM-1849

Scene 56---

Input showing damage caused
by Hurricane Betsy.

NARRATION

run with the re-designed ring produced no apparent overheating. Maximum temperature was reduced approximately 370 degrees in each of more than 100 tests.

A new device, called a four-axis numerical control measuring-inspection machine is being used by Rocketdyne in connection with J-2 injector assembly. It permits time reduction as well as increased reliability of measuring data, and fulfills Rocketdyne's integrated systems approval of using numerical control from design intent to finished component.

At Michoud, clean-up of the facility is still underway as a result of Hurricane Betsy's strike September 9th. The wind and high water forced barges onto land at the Michoud Dock. Superficial damage was experienced by structures, roads and grounds. No impact in schedule is expected as a result of the hurricane.

FILM

Scene 57--

Flight of Super Guppy
to MSFC.

Scene 58---

Summary

NARRATION

The Super Guppy was flown into MSFC September 17th. NASA announced the selection of Aero Spacelines, Inc. of Van Nuys, California for negotiation of a contract to provide air transportation for large cargoes. The Super Guppy is capable of carrying both an S-IV-B and an instrument unit from Marshall to Cape Kennedy.

In summary, the months, July, August, and September witnessed the close of the highly successful Saturn I program and major milestones within the IB program: Preparations for the flight of Saturn IB....,continued Saturn IB stage buildup....., ...activation of Marshall's Battleship Stage Facility..., ...Assembly, delivery and testing of Ground Support Equipment..., ...and new method of transportation.